

An aerial photograph of the Port Everglades facility, showing a large area of construction and expansion. The foreground is a vast, flat, light-colored construction site with some cranes and equipment. In the middle ground, there are numerous stacks of colorful shipping containers (red, blue, yellow, white) and several large gantry cranes. To the left, a large cargo ship is docked at a pier. The background shows the port's edge, some greenery, and distant buildings under a clear sky.

Port Everglades Facility Upgrades

Glenn Wiltshire

Deputy Port Director

Port Everglades Department,
Broward County

www.porteverglades.net/

Anna Dix, SE

Principal

Liftech Consultants Inc.

www.Liftech.net

Juan Anderez, AIA


Architect

Liftech Consultants Inc.


Liftech

Outline

Port Everglades master plan
Facilities overview
Challenges and key decisions
 FAA clearance
 Parallel crane girders
 Facility power
 Project coordination
 Maintain port operations
New ZPMC cranes
Samsung crane upgrades
Summary




Port Everglades Master Plan



Facilities Overview



Before upgrades



After upgrades

G1.1

35'-0" BACKREACH
RAIL
120'-0"
AIRCRAFT CLEARANCE LINE, LEVEL
120'-0"
AIRCRAFT CLEARANCE BREAK POINT
AIRCRAFT CLEARANCE LINE, SLOPED
166'-0" OUTREACH BOOM POSITION C
205'-0" OUTREACH
BOOM POSITION B
130'-0" OUTREACH BOOM POSITION A
BOOM 53.1 AN
TROLLEY DRAWN IN

CAB WASH PLATFORM
CLEARANCE LINE
42'-0"
100'-0"±
20'-0"
10'-0"
50'-0"
6'-6"
BUMPER
CLEARANCE LINE
TIE DOWN ON INSIDE FACE OF LEG SPREADER AND HEADBLOCK STORAGE TOP OF RAIL ELEV. 6.88'
50'-0"
6'-6"
A150 RAIL, TYP
APPROX. 44'-0"
FENCE AT BERTHS 531-33
LIGHT STANDARD FOR LOCATION SEE SHEET G1.1
TENANT YARD
APPROX 200'-0"

TROLLEY PARKED POSITION
"Z" MOTION TO CLEAR BOOM SUPPORT TRUCK, SEE DETAIL 1/M2.1 CABLE REEL
DIESEL GENERATOR ENGINE SET
12'-0"
OPERATING CLEARANCE LINE
FACE OF WHARF
LOCATE REEL TO CLEAR ELEVATOR
7'-3"
8'-4 1/2"
53'-0"
TARGET CONTAINER FOR DETERMINING ABOVE DECK REEVING CLEARANCE WITH HQ LIST
MHW ELEV = +0.39'
119'-10"
128'-6" CLR.
133'-0" AIRCRAFT CLEARANCE LINE
175'-0" ABOVE TOP OF RAIL
41'-0"
47'-6"
5'-0"
14'-0" CLR.
19'-0"
5'-0" FUTURE

- **Lift Height**

Parallel Crane Girders



New ZPMC Cranes

Samsung Cranes

120 ft
(36.6 m)
Rail

100 ft
(30.5 m)
Rail

120 ft (36.6 m) Rail

100 ft (30.5 m) Rail

Facility Power



Turning Notch - Crane Rail Project



08-06-19

Project Coordination



Phase 2

Phase 3


Phase 1: New 120 ft girders and piles at B31-32, electrical infrastructure, and switchgear building

Phase 2: New 100 ft and 120 ft girders and piles at B30 Extension, electrical infrastructure, coordination with turning notch project

Phase 3: New 120 ft girders and piles at B30

Phase 1

Maintain Port Operations



New ZPMC Cranes



Rail Span 120 ft (36.6 m)

Lift Height 133 ft (40.5 m)

Outreach 205 ft (62.5 m)

Backreach 35 ft (10.7 m)

Boom height 26 ft (7.9 m)

Rated Load 66 t (spreader)

Wind Speed 180 mph (80 m/s)

Special features:


- Saddle-type machinery house

- Hoist “Z-motion”

- Boom stowage system

- Boom/crane anti-collision system

Samsung Crane Upgrades



Thank you

This presentation is available for download on our website: www.Liftech.net



Copyright 2024 by Liftech Consultants Inc. All rights reserved.

This material may not be duplicated without the written consent of Liftech Consultants Inc., except in the form of excerpts or quotations for the purposes of review.

The information included in this presentation may not be altered, copied, or used for any other project without written authorization from Liftech Consultants Inc. Anyone making use of the information assumes all liability arising from such use.

Quality Assurance Review:

Author: Anna Dix

Editor: Juan Anderez, Patrick McCarthy

Principal: Erik Soderberg